



TENUGHAT VIDYUT NIGAM LIMITED

तेनुघाट विद्युत निगम लिमिटेड

(A GOVT. OF JHARKHAND UNDERTAKING)

JUPMI Building premises in ABD Area, Ranchi SmartCity,P.O&P.S.Dhurwa,Ranchi-04, (Jharkhand)

NIT No.28/BMD/W/TVNL/RAN/2025-26

Due on -09/01/2026

SRM RFx No-1000012040



TENDER DOCUMENT

**SUBJECT: ANNUAL RATE CONTRACT FOR 02 (TWO) YEARS AND
ANNUAL OVERHAULING OF Mill-BBD, Raw Coal Feeders, Classifiers
etc of Unit-1&2 of TTPS, Lalpania.**



Tenughat Vidyut Nigam Limited

तेनुघाट विद्युत निगम लिमिटेड

(A Govt. of Jharkhand Undertaking)

JUPMI Building premises in ABD Area, Ranchi SmartCity,P.O.&P.S.Dhurwa,Ranchi-04, (Jharkhand)

Ref: 1285/2025-26

Dated :17.12.2025

NOTICE INVITING TENDER

NIT No. 28/BMD/W/TVNL/RAN/2025-26

SRM RFx No-1000012040

On behalf of Tenughat Vidyut Nigam Limited (TVNL), Ranchi online tender is invited (in two parts Part-I - Technical & Commercial Bid, Part-II - Price Bid to be submitted in TVNL's website <https://webdispatcher.tvnl.in/srmprd> only) from experienced, reputed and financially sound firms for annual rate contract for 02 (Two) years and annual overhauling of Mills BBD 4760 BIS, Raw Coal Feeders, Classifiers etc of Unit-1&2 of TTPS, Lalpania. Requisite cost of Tender Document & Earnest Money is to be submitted to contact person of TVNL well before submission deadline. Hard copy of Part-I-Technical & Commercial bid may be submitted in TVNL Headquarter Ranchi on or before due date. The details of Tender are as follows: -

Description of Work	Annual Rate Contract for 02 (Two) years and annual overhauling of Mills BBD 4760 BIS, Raw Coal Feeders, Classifiers etc of Unit-1&2 of TTPS, Lalpania.
Estimated Cost for two years (Rs.)	Rs. 1,47,24,903.63 (Rupees One Crore Forty-Seven Lakh Twenty-Four Thousand Nine Hundred Three and Sixty-Three Paise) only plus GST extra as applicable.
Cost of Tender Documents (Non-Refundable) to be deposited through payment gateway link in TVNL website	Rs. 15,000/- (Rupees fifteen thousand) only. GST@18% Rs. 2,700/- Total Tender fee Rs. /-17,700/- (Rupees Seventeen Thousand Seven Hundred) only.
Amount of EMD to be deposited in the form of BG/payment gateway link in TVNL website.	Rs.2,94,500/- (Rupees Two Lakh Ninety-Four Thousand Five Hundred) only.
Bank Details for BG Creation	Bank Name -ICICI Bank Ltd. Name of Account -TENUGHAT VIDYUT NIGAM Ltd. Branch Name-Lalpur, Ranchi IFSC Code - ICIC0000292
Downloading of Tender Paper	From 22/12/2025
Last date & time of purchase tender paper	08/01/2026 up to 14:00 Hrs.
Last Date & Time for Submission of Tender	09/01/2026 up to 14:00 Hrs.
Date & Time of Opening of Part-I of Tender	09/01/2026 at 16:00 Hrs.
Place of submission of bid documents and address for communication	JUPMI Building premises in ABD Area, Ranchi Smart City, P.O.&P.S. Dhurwa, Ranchi-04, (Jharkhand)

The Bidder should have the following Qualifying Requirements (QR):

1. The Tenderer shall have to submit proof of experience of successfully executed work of Overhauling or maintenance of Mills & its auxiliaries in any Thermal Power Plant not less than 210 MW unit capacity of any TPS under Govt./ Semi Govt. / CPSU/SPSU/SEB's/Reputed Private Organization.
2. The Tenderer is required to submit copy (ies) of work orders as proof of successfully executed work of similar job in Thermal Power Station of unit capacity 210 MW or above during last five years as: -
 - i. Three similar completed works each costing not less than 40% of the estimated cost.
OR
 - ii. Two similar completed works each costing not less than 50% of the estimated cost.
OR
 - iii. One similar completed works costing not less than 80% of the estimated cost."Similar work means the bidder must have successfully executed the work of Overhauling or maintenance of Mills & its auxiliaries in any Thermal Power Plant not less than 210 MW unit capacity under Govt./ Semi Govt. / CPSU/SPSU/SEB's/Reputed Private Organization.
3. The firm has to submit a self-declaration under taking that company has not been blacklisted at the time of submission of bid from any thermal in NTPC/BHEL/SEBs/any PSU.
4. The bidder should have valid GST Registration Certificate along with active GST No., Employee Provident Fund Code No. active PAN and Ownership/Partnership deed, Labour licence and ESI registration.

FINANCIAL CRITERIA: -

i. Average annual turnover of preceding 03 (three) financial years (i.e. 2021-22, 2022-23& 2023-24) should not be less than 30% of the estimated cost. A certificate issued by Chartered Accountant/Auditor should be attached. Annual Accounts Reports of preceding 03 years certified by Auditor/CA for determining, overall profitability, average annual turnover etc, are to be submitted. In case where audited result for the last preceding financial year are not available, certificate of financial statements from a practicing Chartered Accountant shall also be considered acceptable.

ii. Solvency certificate should be of Financial Year 2024-25 or current FY. The bidder should have financial credibility/ Capacity of at least 10% of the estimated cost. Bidder may submit Bank solvency certificate of any Indian Nationalised/Scheduled commercial Bank in support of their financial credibility/capacity.

5. The tender document is to be downloaded from the TVNL website www.tvnl.in. Tenders will have to be submitted in TVNL Web Portal only website:

<https://webdispatcher.tvnl.in/srmprd>

For easy reference "**Vendor Bidding Manual for Open Tender**" can be downloaded from the TVNL website homepage.

6. After advertisement of NIT, intended bidder will first communicate with TVNL contact person EEE(C&M) for this aforesaid NIT only on his Mobile No- No-983127953 and send their firm details well before the submission deadline. Also company's contact person name, email, Mobile no may be sent in email ID: k.ram@tvnl.in, so that login ID & password can be created in SRM-SAP which will be sent to bidders contact person email. Bidder contact person has to register at TVNL website: <https://webdispatcher.tvnl.in/srmprd> with the given ID & password.
7. The cost of tender document and the Earnest Money shall be deposited well before the submission deadline and has to be deposited only through payment gateway link in TVNL website. (DD will not be acceptable). The copy of the transaction ID or receipt may be submitted to TVNL contact person in person or by mail so that the contact person will allow access to open the RFx details and initiate bidding at TVNL website and attach the detail of part - I.
8. Bidder have to fill as well as attach scanned copies of the related documents to qualify in the part-I (Technical & commercial) on TVNL website portal: <https://webdispatcher.tvnl.in/srmprd> and also the bidder may submit the hardcopy of bid part-I (Technical & commercial) to the ESE (C&M), TVNL, JUPMI Building Premises in ABD Area, Smart City, Dhurwa, Ranchi- 834004, Jharkhand office along with the details of paid cost of tender document and paid or BG of Earnest money deposit (EMD).

9. Bidders have to bid for part-II (Price part) on TVNL website:
<https://webdispatcher.tvnl.in/srmprd> only. **Price Part is not to be submitted in Hard copy** (in sealed envelope).
10. Bidder will not get access to bidding in SRM-SAP without providing the details of cost of tender document. Any type of tempering/alteration with tender document shall not be allowed and offer, if submitted so, will be summarily rejected.
11. Tender without Earnest Money shall not be considered. Cost of tender document and Earnest Money Deposit (EMD) of requisite value as specified above is to be deposited well before submission deadline. EMD may be furnished in the form of Bank Guarantee in required format from any Indian Nationalized Bank/ Schedule Commercial Bank in favour of "TENUGHAT VIDYUT NIGAM LIMITED" payable at Ranchi. The Bank Guarantee should remain valid for 12 months. In case BG is to be submitted against Earnest money deposit (EMD) it is to be submitted to TVNL contact person in a separate envelope so that the contact person will enter the BG details against EMD in the respective RFx well before the submission deadline, failing which offers are liable for rejection.
12. The Earnest Money will be forfeited on revocation of tender before expiry of validity of the tender or on refusal to enter into the contract after the award is made by TVNL to the bidder.
13. Any corrigendum/Addendum/Extension of bid opening date and cancellation of NIT will be published through our website www.tvnl.in only and not through newspaper. The bidders are requested to visit our website regularly for any addendum/corrigendum/extension till opening of NIT.
14. The due date of bid opening as mentioned in the tender will remain firm. However, in case of unforeseen circumstances or due to administrative reasons the bids are not opened on the due date, the same shall be opened on the next working day at the same time. In case the last date of submission of bids is declared as holiday, the bids received up to the time of closing of bids on the next working day shall be considered for opening.
15. TVNL reserves the right to reject any / all offer increase/decrease or to distribute the quantity among the bidders without assigning any reason thereof.

Sd/

(R. Ranjan)
Electrical Superintending Engineer (C&M)



TENUGHAT VIDYUT NIGAM LIMITED

तेनुघाट विद्युत निगम लिमिटेड

(A Govt. of Jharkhand Undertaking)

JUPMI Building premises in ABD Area, Ranchi Smart City, P.O&P.S.Dhurwa, Ranchi-04, (Jharkhand)

BILL OF QUANTITY

PART- I (TECHNICAL & COMMERCIAL)

NIT No. 28/BMD/W/TVNL/RAN/2025-26

SRM RFx No-1000012040

Sub: - Annual Rate Contract for 02 (Two) years and annual overhauling of Mills BBD 4760 BIS, Raw Coal Feeders, Classifiers etc of Unit-1&2 of TTPS, Lalpania.

S.N.	Particulars	Details to be furnished by the Bidder (Enclose separate sheets if required)	Flag No.	Page No.
1.	Name of the Bidder (Enclose Letter Head of firm)		I	
2.	Address of Bidder with Telephone, Fax, E-mail		II	
3.	Name of the Proprietor/ Head of the Firm and its key personnel with organizational chart giving details of qualification and experience etc.		III	
4.	Details of maintenance set up with resources like permanent employees (with designation & strength), tools & tackle and other equipment with capacities		IV	
5.	Name and Qualification of the site-in-charge		V	
6.	Working Experience of Bidder (Attach copy of work order of similar work and its successful completion certificate during last seven years as per Sl. No. 1.c of QR)	Work Order No..... Dated..... Completion Certificate Dated..... Work Order No..... Dated..... Completion Certificate Dated..... Work Order No..... Dated..... Completion Certificate Dated.....	VI	
7.	Financial Credibility/ Capacity (Attach Bank Solvency Certificate) Not less than 10% of the estimated cost.		VII	

8.	Average annual financial turnover of bidder during the last 03 years (Attach audited Balance Sheet & P/L Account for last three years ending 31 st March, 2021) not less than 30% of the estimated cost.	Average annual financial turnover of bidder during the last 03 (three) years Rs..... Annual Turnover FY 2021-22: Rs..... FY 2022-23: Rs..... FY 2023-24: Rs.....	VIII	
9.	Name & Designation of Authorized Signatory (Attach Power of Attorney if applicable)		IX	
10.	Nature of Firm (Proprietorship/Partnership /Pvt. Ltd./Public Sector) (Attach proof)		X	
11.	Permanent Account Number (PAN) (Attach proof)		XI	
12.	GST Registration Number (Attach proof)		XII	
13.	EPF. Code No. (Attach copy of registration)		XIII	
14.	ESI Registration			
15.	Particulars of Earnest Money (BG No. & Date or Transaction ID No. and date)		XIV	
16.	Particulars of Cost of Tender Document (BOQ) (Transaction ID No. & Date)		XV	
17.	Any other Tax applicable		XVI	
18.	Whether you accept all term and conditions of B.O.Q.?		XVIII	
19.	Labour Licence		XIX	

20.	Details required for ERP Vendor Coding:- a. Name of firm : b. Address with PIN : c. E-mail ID : d. Phone No. : e. Name of Contact Person: f. TIN No : g. GST No. : h. Active PAN No : Details required for EMD Refund through RTGS/NEFT : i. Bank Name : j. Branch : k. Branch Code : l. A/c. No. : m. IFS Code : n. MICR Code : o. Cancel Cheque:		XX	
21.	Other details and remarks, if any		XXI	

(Signature & Seal of Bidder)

NOTE: - DETAILS SHEET/DOCUMENTS SUBMITTED ALONG WITH BID SHOULD BE FLAGGED. IT IS TREATED AS NECESSARY FOR SUBMISION OF TENDER DOCUMENTS.



TENUGHAT VIDYUT NIGAM LIMITED

तेनुघाट विद्युत निगम लिमिटेड

(A Govt. of Jharkhand Undertaking)

JUPMI Building premises in ABD Area, Ranchi SmartCity,P.O&P.S.Dhurwa,Ranchi-04, (Jharkhand)

NIT No. 28/BMD/W/TVNL/RAN/2025-26.
SRM RFx No-1000012040

Sub: Annual Rate Contract for 02 (Two) years and annual overhauling of Mills BBD 4760 BIS, Raw Coal Feeders, Classifiers etc of Unit-1&2 of TTPS, Lalpania.

INSTRUCTIONS TO BIDDERS FOR ONLINE BIDDING

Due Date & Time of submission of Bids – 09/01/2026 up to 14.00 Hrs

Due Date & Time of Bid opening –09 /01/2026 at 16.00 Hrs.

Each of these instructions must be read carefully and followed strictly. Failure in complying with any of these would render your offer liable for non-submission and TVNL or its any department will not take any responsibility for any bid not successfully Submitted/Participated in **RFx** (Request **for Quotation**).

IMORTANT STEPSFOR PARTICIPATIONIN BIDDING:

If Bidder is interested to participate in the Open tender, then follow the below steps to provide the bid quotation.
Note: Use Only Internet Explorer browser to login into TVNL Portal.

- 1) Open RFx
- 2) Pay tender Fee & Earnest Money Deposit Amount and inform the same to TVNL contact person.
- 3) Click on participate button.
- 4) Click on Create Response Button.
- 5) Enter the Price in the Item tab.
- 6) Click on Technical RFx Button to upload the documents.
- 7) Finally click on Submit button before the Submission deadline date and time.

PAY THE TENDER FEE & EARNEST MONEY DEPOSIT (EMD) AMOUNT

Tender Fee & Earnest Money Deposit may be submitted to TVNL contact person in person or communicate to the contact person by email by attaching the scanned copy of the Demand draft/BG so that the contact person will allow access to open the RFx details and initiate bidding at TVNL website and attach the details of Part-I & fill the details of Part- II.

Inform TVNL contact person to provide the access to RFx to participate in the Bidding.

OPEN THE RFx NUMBER IN THE VENDOR PORTAL

Vendor login: Login to the TVNL Vendor Portal through the URL mentioned below.

Vendor Login URL: <http://webdispatcher.tvnl.in/srmpd>

Login Page shall appear on Vendor Portal page.

Step-1: Enter the User ID and Password and Change the Password during the first login.

Step-2: Click on Logon button

Step-3: Click on **RFx and Auctions**.

Click on Event Number to open the required RFx No. For E.g. 1000000XXX

If Bidder is accessing the bidder portal for the first time then system will show the Register button once you have opened the RFx as shown in the below screen.

For the second time onwards system will not ask for bidder to Register.

After click on Register button, if bidder is not paid the “**Tender fee amount**” to TVNL then system will show the error message as shown in the below screen.

If you get the error message follow the below step:

1) First vendor will pay “**Tender fee & Earnest Money Deposit**” amount and inform the same to TVNL contractor to provide the access to RFx.

Note: Once contact person provide the access to RFx, then bidder will refresh button of the RFx and proceed further.

After the bidder Register, system will show the below options to **Participate, Do Not Participate, Tentative and Create Response.**

What is “Participate” button?

- If bidder click on participate that means, Bidder interested in participating the bidding.

What is “Do Not Participate” ?

- If bidder click on Do Not Participate that means, Bidder is not interested to participate in the bidding.

What is “Tentative” button?

- If bidder click on Tentative that means, Bidder either will participate or not participate in the bidding.

What is “Create Response” button?

- After click on participate/Tentative button, bidder will use the create response to provide his/her bid quotation.

TO CREATE THE RESPONSE FOR THE PARTICULAR RFx

Step-1: Open the RFx.

Step-2: Click on Create Response.

ANSWER THE QUESTIONS IN THE RFx

After clicking on create Response button, system will show the error message. At this time, bidder will follow below steps:-

- 1) Click on Questions tab in the screen
- 2) Bidder will find Questions
- 3) Answer to those questions which are marked “*” is mandatory.
- 4) Finally click on check button to check for any error message.

ENTER THE PRICE OF THE ITEMS IN THE RFx RESPONSE

Enter the Price for all the line items and click on Check if in case of errors and click on Submit to complete the RFx Response.

ASK QUESTIONS TO TVNL IF YOU HAVE ANY DOUBTS REGARDING THE RFx

As a Bidder if You have some questions related to RFx and bidder can also ask questions before submitting the bid.

Step-1: Click on “**Questions and Answers (0)**” button.

Step-2: Enter the Question and click on Send button to send the question to purchaser/TVNL.

Vendor enters the Message and clicks on “**Send**” button.

TO UPLOAD THE DOCUMENTS IN THE RFx RESPONSE AS A BIDDER

Step-1: Click on “**Notes and Attachments**” tab

Step-2: Click on “Collaboration Room” as shown in the below screen to upload the documents.

Step-3: Click on Bidder Document folder.

Step-4: Click on Create Button.

Step-5: Select the Documents to upload the documents

Step-6: Enter the Name, Description of the document and click on Continue

Step-7: Click on Browser button to select the document in your local system.

Step-8: Once the document is selected click on save button.

Step-9: The saved document will be shown.

Step-10: Click on Logout and close the window once you have uploaded all the documents.

TO SUBMIT THE RFx RESPONSE AS A BIDDER

Once you have completed the Price, uploaded the documents click on check button for any errors.

If there is no errors system will show the below message.

Click on Submit button to complete the bidding.

After submitted the system will show the RFx Response status as **“Submitted”**.

You can change the RFx Response even after bid has been submitted only when the submission date or time is still remaining (Not passed).

Step-1: Open the RFx Response

Step-2: Click on Edit Button

Step-3: Make changes in the RFx Response and Click on Submit.

You can also click in the Withdraw button to withdraw a bid and then If you Click on Edit button after withdrawal you can again make changes and resubmit the RFx Response if the submission time is remaining.

ONLINE PAYMENT PROCESS

After registering against the RFx you have to follow the below steps:

1. Go to TVNL website <http://tvnl.in>
2. Click on the navigation tab “ Tender Payment” link (at the Top Right hand side of the TVNL web home page).
3. It will redirect you to the online payment page.
4. Enter your User Id to proceed further.
5. Enter the RFx no. for which you want to participate.
6. Click on the “Go” button.
7. Click on the Pay button to proceed for payment of “Tender Fee” or “EMD”.
8. It will redirect you to the payment gateway for payment.
9. Enter your card details or go for online banking for payment.

(Signature & Seal of Bidder)



TENUGHAT VIDYUT NIGAM LIMITED

तेनुघाट विद्युत निगम लिमिटेड

(A Govt. of Jharkhand Undertaking)

JUPMI Building premises in ABD Area, Ranchi Smart City, P.O&P.S.Dhurwa, Ranchi-04, (Jharkhand)

NIT No. 28/BMD/W/TVNL/RAN/2025-26.

SRM RFx No-1000012040

Sub: -Annual Rate Contract for 02 (Two) years and annual overhauling of Mills BBD 4760 BIS, Raw Coal Feeders, Classifiers etc of Unit-1&2 of TTPS, Lalpania.

GENERAL TERMS & CONDITIONS

- 1. Validity of Offers:** The bid submitted by the bidders should remain valid for a minimum period of 120 days from the date of opening of Part-I unless otherwise specified.
- 2. Prices:** - The Bidder shall quote their rate keeping in view that the rate will remain firm for the entire contract period of 02(two) years.
No extra amount against increase in works/any other by Govt. will be payable by TVNL to the contractor during the entire contract period.
- 3. Late Receipt of the Tender:** Special attention of the bidder is invited about the receipt of the tender in time. Tenders received after the stipulated date and time due to any reason, whatsoever, shall not be considered. Bidders are requested to see that their bids are delivered in the office of TVNL before the prescribed date and time.
- 4. Inspection of Site:** Before quoting the rate, bidders are advised to visit the work site and get satisfied with scope of work for which rates are to be quoted. Engineer -in -charge may be consulted for any clarification regarding scope of work and terms of tender. Bidder should go through the terms and conditions and technical specifications of work carefully and sign in all pages of the tender document.
- 5. Instruction to Bidder:**
 - a.** Bidders are advised to submit their bids strictly based on the scope of work, terms and conditions contained in the bid document and subsequent revisions/amendments, if any. The bid should be submitted along with covering letter.
 - b.** The bid shall be prepared and submitted by typing or printing in English on white paper in consecutively numbered pages duly signed by the authorized signatory with company seal affixed on each page. Any part of the bid, which is not specifically signed by the authorized signatory and not affixed with company seal, may not be considered for the purpose of evaluation.
 - c.** Copy of bid document, amendments/revisions to bid document if any, shall be signed and submitted along with the bid.
 - d.** Complete bid document including all enclosures should preferably be submitted in hard bond or spiral binding and all pages should be numbered and must be signed by the authorized signatory with seal of the company.
 - e.** Incomplete tender or tenders not submitted as per requirement as indicated in the NIT are likely to be rejected.

- f. Bidders shall submit their offer strictly as per terms and conditions of the tender document without any deviation. If at any time any of the documents/information submitted by the bidder is found to be incorrect, false or untruthful, the bid and/or the resultant order may be summarily rejected/ cancelled at the risk of the bidder.
- g. Failure to furnish all information and documentary evidence as stipulated in the bid document or submission of an offer that is not substantially responsive to the bid document in all respects shall be summarily rejected.
- h. All bids will be received in duly sealed cover within the due date and time. Bids received after the due date and time is liable for outright rejection.
- i. Variation may occur in the quantity of items required to be executed under this contract depending on the condition of machine and availability of units.

6. Earnest Money Deposit (EMD): Offers shall be accompanied with Earnest Money Deposit (EMD) of requisite value as specified in a separate envelope failing which offers are liable for rejection. EMD may be furnished in the form of Bank Guarantee from any Indian Nationalized Bank/Schedule Commercial Bank in favour of "TENUGHAT VIDYUT NIGAM LIMITED" payable at Ranchi. The Bank Guarantee should remain valid for 12 months or may be deposited through payment gateway link of TVNL website. The earnest money will be forfeited on revocation of tender before expiry of validity of the tender or on refusal to enter into the contract agreement after the award is made by TVNL to the bidder.

Tenders without Earnest Money shall not be considered other than NSIC/SSI (Jharkhand) registered units. A copy of such registration has to be furnished for claiming exemption from EMD. Exemption from the Earnest Money to NSIC/SSI units will be considered as per Govt Circulation. SSI units of Jharkhand will be given preference as per Govt rule.

7. Security Deposit: The successful bidder shall have to deposit total security deposit @ 10% of order value in which initial security money @5% of the order value (including earnest money) will be retained as security deposit. Initial security money will be accepted as Bank Draft/ Bank Guarantee in the prescribed format not adjustable against running bill. The security deposit shall have to deposit well before execution of the Agreement. Balance 5% of security money will be deducted from R/A bills. The security money will be released after successful completion of work and closure of contract.

8. Payment Terms: Payment of Contractor on actual measurement basis will be made through running bills which will be verified by Engineer -in-Charge after successful completion of the work and payment of wages to the employee by the Contractor. The bill in triplicate will be submitted by the Contractor to the Engineer -In-Charge along with Bank Statement and Payment sheet showing payment of wages to workmen and other relevant documents like EPF & GST deposit slip etc before release of payment.

- 9. Paying Authority:** The Accounts Officer, TTPS, Lalpania will be the Paying Authority.
- 10. Engineer-in-Charge:** Concerned Electrical Executive Engineer will be the Engineer-in-Charge for this work. The works are to be executed as per direction of Engineer-in-Charge. Anything not mentioned here in shall be decided by the Engineer- In- charge of the work and shall be binding on the contractor.
- 11. Period of Contract:** The period of contract shall be 02 (two) years from the date as shall be mentioned in the work order.
- 12. Safety Measures:** The Contractor shall observe all the safety measures. Safety appliances have to be arranged by the Contractor at his own cost. Any compensation payable to the Contractor's employee in the event of accident or causality has to borne by the Contractor himself and TVNL will not be responsible on this accounts in any way. In case of any damage due to negligence mishandling and mal operation by the staff of contractor, the damage would be made good by the contractor at his own cost. In case of non compliance, proportionate deduction will be made from the bills of the contractor. The contractor shall provide all safety appliances, tools and equipments to his staff and ensure that those items will use by all staff while working and on whole duty period. Name of such important items are given below:-
- i. Asbestos hand gloves, Apron Asbestos cloths etc.
 - ii. Rubber & Leather hand gloves,
 - iii. Safety shoes for all types of works,
 - iv. Safety belts and hooks,
 - v. Helmets, Ear muffs, Safety goggles, Nose muffs etc.
 - vi. Any other items related to safety rules may be assumed in contractor's scope
- 13. Scope of the work:** Scope of the work is attached here as a guideline to execute the work. However contractor has to execute all the work as per direction of Engineer-in-Charge for proper working of equipments.
- 14. Labour Laws:** The bidder has to follow the guidelines laid under the labour law, workmen compensation, and EPF rules in respect of minimum wages, EPF payment and other service conditions. In the event of any accident / casualty to the employees of contractor, the compensation payable to the employees is to be borne by the contractor and TVNL will not be responsible in any way.
- 15. Minimum Wage Guarantee:** The contractor shall strictly ensure that the minimum wages as stipulated by GoJ from time to time is paid to their workmen. Any increase in minimum wages during the period of contract, will have to be paid to their workmen without any claim on TTPS/TVNL. If the contractor fails to comply with guarantee of minimum wages then the agreement is liable to be terminated and security money may be forfeited.
- 16. Taxes:** All statutory taxes as applicable shall be deducted from each running bill of contractor.
- 17. Violation of Terms & Conditions of Tender:** All terms and conditions of tender shall form a part of the contract. If contractor fails to execute the work up to entire satisfaction of Engineer -in -Charge as per terms & conditions of tender, then the contract agreement can be terminated on one month prior notice and security money shall be forfeited.
- 18. Subletting:** The successful bidder will have to execute the work directly. No subletting will be allowed.

- 19. Competent Authority:** During the execution of work in case of any dispute between the Engineer-in -Charge and contractor, the decision of General Manager cum Chief Engineer Tenughat TPS will be final and binding.
- 20. Man Power:** A list of manpower arranged by the contractor should be submitted to Engineer -in -Charge of the work before deployment and same should be deployed with due permission of Engineer -in -Charge. If the performance of the deployed person is not found up to the mark at any time, the contractor will have to replace them with experience and suitable person. During the period of absence of contractors personnel TVNL will have right to deduct penalty from contractor's bill.
- 21. Tools & Tackles:** The contractor should have to arrange all tools & tackles as per scope of work whereas heavy tools like hydra crane will be arranged by TTPS if available as per request of contractor. Contractor will arrange standard make tools after getting approval from EIC. Contractor will arrange welding M/C, gas cutting set etc to carry out any mechanical work in maintenance of field instruments as and when required. The entry of tools and tackles inside the power house should be verified by the CISF and should match with the requirement. Pro-rata deduction will be made if any mismatch is found. Agency must arrange 02 nos. of master levels, 02 nos. of dial gauge and 02 nos. of vernier, sufficient nos. of filler gauge for leveling and measurement job at site. All above mentioned equipments must be in good condition.
- 22. Consumables:** The contractor has to provide all consumables like gas, electrodes, cotton waste, markin cloth, rustolin, K-Oil, Petrol/Diesel and abrasive materials at their own cost, if required and applicable. The entry of consumables inside the power house should be verified by the CISF and should match with the requirement. Pro-rata deduction will be made if any mismatch is found.
- 23. Site Cleaning:** The Contractor must keep the working areaclean after completion of the job. Waste materials and garbage shall be disposed off by the contractor at suitable place as per the instruction of the Engineer-in-Charge. Old unserviceable spare parts if so, has to be returned by the contractor to the Central Store/Site Store of TTPS as per the instruction of the Engineer-in-Charge.
- 24. Facilities to be provided by TVNL:**
- a. Unfurnished accommodation for office with water and electricity inside the power house will be provided free of cost if available.
 - b. The contractor shall be allowed to avail the facilities to extent available at our Chemical Lab at TTPS.
 - c. Guest house facility shall be provided to the visiting engineers/officers of the Contractor on chargeable basis if available.
 - d. Unfurnished accommodation may be provided to the employees of the Contractor, if available during the period of execution of work on rental basis as per departmental rule.
 - e. Electricity will be provided on chargeable basis as per JBVNL Tariff.
 - f. Medical facility as available at project site shall also be extended to the employee of the contractor. No payment will be made for any medicine purchased from outside or any treatment or test done outside the TTPS Hospital.
- 25. Working Administration:** In general working hours of the TTPS employee will be the working hours of employee of Contractor. However in case of emergency or as per requirement of the job, contractor's employees will be required to work beyond working hours and also on rest days and holidays on the direction of Engineer -in -Charge. Employees deployed by the contractor will be under the operational control of Engineer -in -charge. In case of any employee working in shift/general duty falling sick or proceeding on leave the facts shall be brought to the knowledge of Engineer -in -Charge and deficit will be made by the contractor either by the existing staff by performing overtime duty or getting other manpower without adding any additional cost to the Project. If the shift remains vacant the penalty will be deducted from the contractor's bill. It shall be binding on contractor that it does not directly or through its personnel divulge the secrecy of the

establishment of TTPS. Any person deployed by contractor will not be a member of any trade union operating in the TTPS Projects establishment or outside. They will not take part in any strike or sympathized with any such movement.

26. Penalty: In case of any breakdown, fault or emergency maintenance, the contractor has to attend the same without any delay. In case of failing or deliberated neglect, the work will be carried out through outside agency at the cost & risk of the contractor and this may be liable for termination of their contract. A poor (Manpower: skilled or unskilled, T&P and consumables) mobilization during OH or Emergency jobs shall attract a penalty of Rs 5000/ per day. Further any safety lapses like non use of PPEs, improper handling of gas cylinders, improper power connection, damaged electrical equipments, non use of plug tops, inadequate scaffolding where work is being carried out at height, poor/absence of temporary fencing where railing has been cut to facilitate lifting up or/and down of materials etc shall attract a penalty of Rs 5000/ per occasion. Scrap generated during the work shall be removed every day(as directed by EIC) by the contractor to keep the area clean. If scrap is not removed then the same will be removed at risk and cost of agency @ Rs 5000/MT will be deducted as penalty.

27. Departmental Facilities: In case of major repair of equipments and testing of special equipments contractor should have to provide services of an expert from manufacturer and special tools & tackles. The contractor will also provide all other technical staffs and T&P's consumables etc free of cost. However, all spares parts shall be provided by TVNL on free of cost.

28. Transportation: Successful bidder will be required to arrange his own conveyance for their employee for attending their duties.

29. Mobilization Time: The successful bidder will be given maximum 15 days time from the date of LOI / Work Order for Mobilization of resources, manpower to start the work. However for the work under ARC, contractor shall be given the mobilization period of one day. The contractor should be in position to ensure mobilization even within shorter period to start the work if need so arises like availability of the shutdown of units. No extra claim shall be entertained by either for idle labour or reduced mobilization period.

30. Agreement: The firm or his legally authorized representative having Power of Attorney will have to execute an agreement with the ordering authority within 25 days of issue of order in the event of placement of order on them. The agreement will have to be prepared on a non-judicial stamp paper of Rs.100/- only on Nigam's format. Bank Guarantee against Security Deposit, Performance Guarantee etc. as per order will have to be furnished well before execution of agreement. The contractor is required to produce all original paper and documents for verification before agreement failing which order will be cancelled. Contractor will not be allowed to start the work without executing the agreement.

31. Jurisdiction of Court: Any dispute between the Contractor and TVNL shall be settled in the Civil Court, Ranchi, Jharkhand only.

(Signature & Seal of Bidder)



TENUGHAT VIDYUT NIGAM LIMITED

तेनुघाट विद्युत निगम लिमिटेड

(A Govt. of Jharkhand Undertaking)

JUPMI Building premises in ABD Area, Ranchi Smart City, P.O&P.S.Dhurwa, Ranchi-04, (Jharkhand)

NIT No. 28/BMD/W/TVNL/RAN/2025-26.

SRM RFx No-1000012040

Sub: Annual Rate Contract for 02 (Two) years and annual overhauling of Mills BBD 4760 BIS, Raw Coal Feeders, Classifiers etc of Unit-1&2 of TTPS, Lalpania.

Scope of work

SERVICE LINE 10: SCOPE OF WORK-

- (1) External cleaning of mill and its platform.
- (2) Positioning of the mill.
- (3) Opening the manhole doors & making arrangement for internal checking of the mill .
- (4) Tie Rods, Ribbons, Ribbons Fix ed Ends Checking for any damaged chain & chain links, Ribbon Support angles, trunion tube checking for any damage.
- (5) Screw conveyor body liner condition checking for any damage due to wear & tear.
- (6) Delta P Nozzle, Nozzle guards (C&I) checking .
- (7) Shell liners condition checking, Shell Flange inspection for any gap .
- (8) Close the man hole doors.
- (9) Remove of all scraps from work center and disposal in scrap yard.
- (10) Clean the area and boxed up the mill.

SERVICE LINE 20: SCOPE OF WORK:-

- (1) External cleaning of mill and its platform.
- (2) Opening the manhole doors and makes arrangement for repairing of Helixes.
- (3) Identification of damaged potion of the helix.
- (4) Removal of damaged portion by gas cutting.
- (5) Transport Helix from central store to work place.
- (6) Cutting helix in required size after taking measurement.
- (7) Welding it at damaged portion.
- (8) Close the man hole doors.
- (9) Remove all garbage and scaffoldings.
- (10) Clean the area and boxed up the mill.

SERVICE LINE 30: SCOPE OF WORK: -

- (1) External cleaning of mill and its platform.
- (2) Opening the manhole doors and make arrangement for repairing of chain.
- (3) Identification of damaged chain and chain links.
- (4) Removal of damaged chains by gas cutting.
- (5) Transport chain links from central store to work place.
- (6) Cutting damaged chain link.
- (7) Replace damaged chain link & repair broken chain.
- (8) Close the man hole doors.
- (9) Remove all garbage and scaffoldings.
- (10) Clean the area and boxed up the mill.

SERVICE LINE 40:**SCOPE OF WORK:-**

- a) Open manhole doors.
- b) Identifying the damaged portion of drum (DE & NDE side)
- c) Removal of damaged angles.
- d) Welding new angles,
- e) Repair conveyor body, hot air box manholes doors, cutting of damaged skid plate and repair by welding special Lotharm-468 electrodes.
- f) Close the man hole doors.
- g) Remove all garbage and scaffoldings.
- h) Clean the area and boxed up the mill.

SERVICE LINE 50:

Mill-Repairing-hot air box & internals ms welding.

- a) Open manhole doors of hot air box.
- b) Identifying the damaged portion of internal and hot air box(DE & NDE side).
- c) cleaning of hot air box/tube.
- d) Repairing of hot air box and internals of mills by MS welding.
- e) Close the man hole doors.
- f) Remove all garbage and scaffoldings.
- g) Clean the area and boxed up the mill.

SERVICE LINE 60:

Replacement of drive bar with stiffeners of MILL

- 1)) Opening the manhole doors and make arrangement for replacement of drive bars and stiffeners
- 2) Identification of damaged drive bars.
- 3) Removal of damaged drive bars and stiffeners by gas cutting.
- 4) Cleaning the bush of any foreign materials,
- 5) Transport drive bars and stiffeners from central store to work place.
- 6) Fitting new drive bar and stiffeners.
- 7) Welding the bush with LO-Therm welding ,
- 9) Close the man hole doors.
- 10) Remove all garbage and scaffoldings.
- 11) Clean the area and boxed up the mill.

SERVICE LINE 70:

OVER HAULING / SERVICING OF GREASING SYSTEM OF GIRTH GEAR.

- 1) Stop the greasing system of mill.
- 2) Checking for any leakage from the system.
- 3) Tightening of all the joints.
- 4) Replacement of all hoses.
- 5) Open the main greasing system door.
- 6) Cleaning the grease filter/ Replaced filter if required.
- 7) Cleaning of all six nozzles of greasing system.
- 8) Replacement of distributor block if required.
- 9) Replacement / Revisioning of grease pump.
- 10) Thorough checking grease line from pump discharge to distributor block.
- 11) Close the system.
- 12) Remove all scraps and scaffoldings from work center.
- 13) Taking trial run of grease system and rectify if any found.

SERVICE LINE 80:**SCOPE OF WORK:-**

REPLACEMENT/SERVICING OF BALL FEEDING GATE OF MILL

- 1) Take PTW from the area engineer for attending the defect/ball feeding gate
- 2) Removal of actuator from gate shaft.
- 3) Gate blade to be separated from top & bottom cover .
- 4) checking of gate blade condition and if found unusable then replace the gate blade.
- 5) Cleaning of V-grooves /shaft threads by diesel & air.

- 6) Replacement of damaged gaskets & seals, assembly .
- 7) Operation checking of actuator and gate operation with exact fitting in grooves.
- 8) Clean the work centre immediately after work completion.

SERVICE LINE 90:

SCOPE OF WORK:-

COMPLETE OVERHAULING OF LUB OIL SYSTEM OF MILL

- 1) Stop the milling system with its lubrication .
- 2) Isolate water line and oil line from pump and cooler.
- 3) Drain the oil from oil tank and collect oil in empty drum.
- 4)Clean the oil tank, oil pipe line, nozzles ,water lines .
- 5)Replacement pumps and NRV if required.
- 6) Clean the cooler.
- 7)Fitting cooler and connect water and oil line.
- 8) Connect all oil lines from pumps and tank.
- 9) Charge all line of oil and water.
- 10) Take trial run and rectify leakage if found.
- 11) Removal of all scraps from work center to scrap yard.
- 12) Clean the work center immediately after work completion.

SERVICE LINE 100:

SCOPE OF WORK:-

CHECKING AND DEFECT RECTIFICATION OF MAIN SPEED REDUCER GEAR BOX OF MILL

- 1) Stop the milling system.
- 2) Opening the top inspection hole.
- 3) Checking for proper spray of lubricant on gears/pinion and adjustment of lub. Oil line if needed.
- 4) Checking the flow and pressure. of the reducer lub oil pump.
- 5) Backwashing of the cooler.
- 6) Cleaning of the filter and replace if required.
- 7) Removal all scraps.
- 8) Clean the work centre immediately after completion of work.
- 9) Take trial run in auxiliary motor and rectify defect if any found.

SERVICE LINE 110:

SCOPE OF WORK:-

ALIGNMENT OF TOTAL DRIVE SYSTEM OF MILL

- 1) Stop the milling system with its lubrication.
- 2) Decouple the LS coupling first .
- 3) Take alignment reading and coupling gap, compare it with the erection data sheet, do the correction if required.
- 4) couple the LS coupling .
- 5) Decouple the HS coupling.
- 6) Take alignment reading and coupling gap. compare it with the erection data sheet, do the correction if required.
- 7) Couple the HS coupling.
- 8) Take Trial of the mill in Auxiliaries motor.
- 9) Removal of all scraps from work centre
- 10). Clean the work centre immediately after completion of work.

SERVICE LINE 120:

SCOPE OF WORK:-

REPLACEMENT SEALING OF SCREW CONVEYOR STUFFING BOX.

- 1) OPEN MAN HOLE OF MILL.
- 2) REMOVAL OF THE SEAL FLANGE.
- 3) TAKING OUT THE DAMAGED GLAND ROPES.
- 4) CLEANING OF THE GLAND PORTATION.
- 5) FITTING OF NEW GLAND ROPE IN THE GROOVE.
- 6) TIGHTNING OF THE FLANGE OF GLAND.
- 7) CLEAN THE INTERNAL AND EXTERNAL OF WORK CENTRE.

- 8) TAKING TRIAL RUN AND ATTENDING LEAKAGE IF ANY FOUND.
- 9) REMOVE ALL SCRAPS IMMEDIATELY AFTER COMPLETION OF WORK.

SERVICE LINE 130:

SCOPE OF WORK:-

Mill -Revisioning of countershaft bearing.

- 1) Removal of side cover of bearing housing.
- 2)Removal of top cover of bearing.
- 3) cleaning of counter shaft bearing.
- 4) Removing the side plates/ring.
- 5) Removing burnt grease and clean.
- 6) Removing the lock nut, checking the condition of roller/cage and sleeve.
- 7) Taking clearances of the bearing and rectify it if found any difference.
- 8) Fit lock nut in place.
- 9) Put top cover and tightening the top cover.
- 10) Applying grease and box-up of bearing.
- 11) Clean the work centre.
- 12) Take trial run and attending defects found if any.
- 13) Removal all scraps from work centre immediately after completion of work.

SERVICE LINE 140: SCOPE OF WORK:-

Replacement of screw conveyor body liners of VAR-I, II & III type and patch work of damaged portions:

- 1) Opening of the shell doors as required for the work.
- 2) Loosening the liner bolts & removal of old liners.
- 3) Liners to be replaced with new ones & to be bolted with new bolts/ nuts/washers after applying Packing materials if required as per instruction of E-I-C
- 4) Closing of man hole doors Torque tightening as per instruction of the E-I-C.
- 5) Closing of man hole doors
- 6) Shifting of all the damaged liners to central stores
- 7) Identifying damaged portion of screw conveyor body
- 8) Removal of damaged portions by gas cutting.
- 9) cutting Plates of required size, patching by ms welding.
- 10) Cleaning of the working area immediately after completion of work.

SERVICE LINE 150:

SCOPE OF WORK:-

REPLACEMENT OF AUXILIARIE REDUCER FLUID COUPLING

- 1) Decouple the aux motor with fluid coupling from brake drum.
- 2) Remove the aux motor with fluid coupling.
- 3) Take out the fluid coupling by using suitable puller.
- 4) Fit the New /Repaired Fluid coupling.
- 5) Place the motor With fluid coupling on foundation.
- 6) Take alignment.
- 7) Couple it with brake drum.
- 8) Clean the equipment and work area after completion of work.
- 9) Take trial run of equipment.

SERVICE LINE 160:SCOPE OF WORK:-

REPLACEMENT OF NRV OF HP AND BALL & SOCKET PUMP OF MILL

- 1) Take PTW from the area engineer for attending the defects.
- 2) Stop the lubrication system of mill.
- 3) Dismantle the concerned discharge unit.
- 4) Clean the equipments by compressed air thoroughly.
- 5) Replace the defective NRV /relief valve/connecting pipes.
- 6) Tighten all the joints.
- 7) Take trial run and attending leakage if any found.
- 8) Identify the proper work of NRV/ Relief valve.
- 9) Clean the work centre after completion of work.

SERVICE LINE 170SCOPE OF WORK:-

REPLACEMENT/REPAIR/OVERHAULING OF AUXILIARIE REDUCER GEAR BOX

- 1) Decouple the aux. Reducer from main motor and Aux. Motor.
- 2) Removal of top cover.
- 3) Cleaning of all internals inside the gear box,
- 4) Inspection of internals of gear box like bearing checking .pinion checking. and detection of fault (if any)
- 5)Replacement of defective internals for satisfactory operation of gear box or position of gear box after proper cleaning of parting plane and fitting of top cover./REPLACEMENT OF GEAR BOX.
- 6) Cleaning and machining the key ways emery paper grinding.
- 7) Fitting of couplings.
- 8) Cleaning of foundation and checking of its surface by blue matching with a glass plate.
- 9) Cleaning of concerned area after maintenance work.

SERVICE LINE 180

SCOPE OF WORK:-

REPLACEMENT OF HELIX BOTH SIDE OF SCREW CONVEYOR(1 SET= 4 NUMBERS OF HELIX)

- 1) Stop the mill.
- 2) Open the conveyor body and shell manholes.
- 3) cut the screw conveyor ribbons to be replaced.
- 4) Place the new ribbons/helix inside the mill through manhole.
- 5) Do the alignment of new helix.
- 6) Tack weld with chains.
- 7) Again check for equal gap.
- 8) Weld chain with helix.
- 9) Remove all scraps from mill.
- 10) close all the manholes .
- 11) Take trial run and if found any abnormalities in Helix attend immediately.
- 12) Clean the work centre immediately after completion of work.

SERVICE LINE 190

SCOPE OF WORK:-

REPLACEMENT OF SCREW CONVEYOR BEARING SLEEVE.

- 1) Open the manhole doors and Open the bearing housing bolts.
- 2) Support the screw conveyor shaft from inside and outside to avoid any deformity.
- 3) Remove the bearing housing.
- 4) Remove the old bearing.
- 5) Clean the housing and bearing.
- 6) Place the new/ cleaned old bearing.
- 7) Put the bearing housing in position.
- 8) Do the alignment of screw conveyor by inching.
- 9) Box up all the manholes and bearing housing after proper greasing.
- 10) Remove all the scraps from the site.
- 11) Clean the work centre immediately after completion of work.
- 12) Take trial run and attend defect if found any abnormalities in screw conveyor bearing.

SERVICE LINE 200

SCOPE OF WORK:-

REPLACEMENT OF HP PUMP / BALL & SOCKET PUMP OF MILL.

- 1) STOP THE MILL AND ITS LUBRICATION SYSTEM.
- 2) CLOSE THE SUCTION AND DISCHARGE SIDE OF DEFECTIVE PUMP(AS APLICABLE).
- 3) OPEN THE SUCTION AND DISCHARGE OF PUMP.
- 4) DECOUPLE THE PUMP FROM MOTOR.
- 5) REMOVE THE DEFECTIVE PUMP.
- 6) FIT REPAIRED OR NEW PUMP AND TIGHTENED THE BASE BOLT.
- 7) COUPLE THE PUMP WITH MOTOR.
- 8) TIGHTEN THE SUCTION AND DISCHARGE LINE OF PUMP.

- 9) TAKE TRIAL RUN OF PUMP AND ATTENDED LEAKAGE IF ANY FOUND.
- 10) REMOVE OLD/ DEFECTIVE PUMP AND PLACE IT IN SITE STORE AS PER E-I-C.
- 11) CLEAN THE WORK CENTRE IMMEDIATELY AFTER COMPLETION OF WORK.

SERVICE LINE 210

SCOPE OF WORK:-

REPLACE THE COOLER OF MILL /REDUCER.

- 1)ISOLATE THE COOLER FROM WATER AND OIL SIDE.
- 2) REMOVAL OF WATER AND OIL CONNECTION FROM COOLER.
- 3) LOOSENING THE FOUNDATION BOLTS OF COOLER.
- 4) REMOVAL OF THE DEFECTIVE COOLER.
- 5) PLACE NEW / REPAIRED COOLER IN PLACE OF DEFECTIVE COOLER.
- 6) CONNECTING THE OIL LINE AND WATER LINE.
- 7) TIGHTEN THE BASE BOLT.
- 8) CHARGE THE OIL LINE AND OBSERVED LEAKAGE.
- 9) CLOSE THE OIL LINE AND CHARGE WATER LINE AND AGAIN OBSERVE WATER LEAKAGE.
- 10) IF FOUND HEALTHY THEN CHARGE BOTH LINE WATER AND OIL.
- 11)SHIFTING THE DEFECTIVE COOLER AND PLACE IT AS PER E-I-C.
- 12) CLEAN THE WORK CENTRE AFTER COMPLETION OF WORK.

SERVICE LINE 220

SCOPE OF WORK:-

REPLACEMENT OF DAMAGED SHAFT SCREW CONVEYOR ASSEMBLY

- 1) STOP THE MILLING SYSTEM.
- 2) MAKE ARRANGEMENT AND SCAFFOLDING FOR WORK.
- 3)REMOVAL OF ALL THE LOCKING BY GRINDING CUTTING.
- 4) ARRANGEMENT OF SUITABLE FIXTURE FOR TAKING OUT THE SHAFT WITH THE HYDRAULIC JACK.
- 5)ALTERNATELY CUTTING OF THE HUB.
- 6) REMOVAL OF THE SHAFT.
- 7) TRANSPORT NEW SHAFT FROM CENTRAL STORE TO WORK CENTRE.
- 8) FITTING THE NEW SHAFT AND WELD WITH LO-THERM 468 ELECTRODE AS PER REQUIREMENT.
- 9) CLEAN THE WORK CENTRE INTERNAL AND EXTERNAL.
- 10) BOX-UP THE SYSTEM.

SERVICE LINE 230

SCOPE OF WORK:-

REPLACEMENT OF CYLINDRICAL/ OBLIQUE WAVE LINERS(400 NOS.OF CYLINDRICAL AND OBLIQUE WAVE LINERS

- 1) OPEN THE MAN HOLE DOORS.
- 2) MAKE ARRANGEMENT AND SCAFFOLDINGS FOR WORK.
- 3) CLEANING THE SHELL BODY LINER PORTATION.
- 4) IDENTIFY THE DAMAGED LINERS.
- 5) REMOVE THE DAMAGED LINERS BY GAS CUTTING.
- 6) TRANSPORT NEW LINERS FROM CENTRAL STORE.
- 7) PLACE NEW LINERS IN PLCE OF DAMAGED LINERS.
- 8) FIXED IT BY PLUGGING WITH WELDING.
- 9) CLEAN THE WORK CENTRE.
- 10) REMOVE ALL SCRAPS FROM WORK CENTRE TO STEEL YARD.
- 11)BOX-UP THE MILL.
- 12) TAKE TRIAL RUN AND ATTEND DEFECTS IF ANY FOUND.

SERVICE LINE 240

SCOPE OF WORK:-

REPLACE LONG/ SHORT CONICAL LINERS.

- 1)Opening the man hole doors.
- 2) make arrangement and scaffoldings for work.
- 3) Transport liners from central store to work centre.
- 4), Cleaning the shell body liner portion.
- 5) Identifying the damaged liners.
- 6) Removal of the damaged liner by gas cutting.

- 7) Placing new liners in place of damaged liners.
- 8) Fixing it by plugging with welding.
- 9) Clean the work centre internal and external.
- 10) Box-up the milling system.
- 11) Take trial run and attending defects if any found.

SERVICE LINE 250

SCOPE OF WORK:-

REPLACEMENT OF LINERS / INLET LINER-BOSS OF MILL

- 1) Shell to be rotated to suitable position for easy removal of shell liners.
- 2) Opening of the shell doors as required for the work.
- 3) Loosening the liner bolts & removal of old liners.
- 4) Transport liners from central store to work centre.
- 5) Liners to be replaced with new ones.
- 6) Bolted it with new bolts/nuts/Washers after applying packing materials if required as per instruction of E-I-C.
- 7) Torque tightening as per instruction of the E-I-C.
- 8) Sound hood structure is to be reassembled.
- 9) Man hole doors to be closed.
- 10) Rechecking of tightness of the liner bolts after mill is rotated for 7 to 8 hours.
- 11) Shifting of all the damaged liners to central stores
- 12) Cleaning of the working area after completion of work.

SERVICE LINE 260

SCOPE OF WORK:-

REMOVAL HOT AIR TUBE INSIDE AND OUT SIDE AND FITTING AFTER REPAIRE.

- 1) Open mill shell.
- 2) Open screw conveyor and main PA duct manholes.
- 3) Remove all the drum tightening bolts .
- 4) Remove screw conveyor inside /outside the mill.
- 5) Refitting of the hot air tube/screw conv. Assy. after repair.
- 6) Tightening of all the bolts.
- 7) closing of all the manholes of shell and PA duct & screw conveyor.
- 9) Removal of all scraps from work centre to yard.
- 10) Clean the work place after completion of work.
- 11) Take trial run and attending defects if any found

SERVICE LINE 270

SCOPE OF WORK:-

REPAIRING / OVERHAULING OF MAIN SPEED REDUCER OF MILL.

- 1) Draining of oil through trays in empty drums.
- 2) Opening of top cover of gear box. Dismantling of gear coupling and resilient coupling from old gear box.
- 3) Dismantling of oil cooler and cooling lines.
- 4) Removal of top cover, cleaning of all internals inside the gear box, inspection of internals of gear box like bearing checking (06 nos.), pinion checking (1st, middle and 3rd) etc.
- 5) detection of fault (if any) replacement of defective internals for satisfactory operation of gear box, or position of gear box after proper cleaning of parting plane and fitting of top cover.
- 6) Decoupling of L.S. and H.S. coupling. taking out both LS and HS coupling by heating.
- 7) Cleaning and matching the key ways with emery paper grinding.
- 8) Fitting of taken out coupling on both input and output shaft of the gear box with heating.
- 9) Loosening of all the foundation bolts.
- 10) Cleaning of base plate of gear box and checking of its surface by blue matching with a glass plate.
- 11) Oil top-up in gear box up to required level and checking oil flow to bearings, gear teeth etc. through inspection doors.

SERVICE LINE 280

SCOPE OF WORK:-

REPLACEMENT OF LS COUPLING.

- 1) Draining of oil through trays in empty drums.
- 2) Opening of top cover of gear box.
- 3) Dismantling of gear coupling between reducer and Countershaft.

- 4) Taking out output shaft assembly through EOT crane and placing it properly on wooden planks.
- 5) Removal of coupling Halves from countershaft and output shaft assembly by heating.
- 6) Thorough cleaning of the coupling portion of both shafts.
- 7) Fitting new Coupling halves in both shafts by heating.
- 8) Cleaning and checking of pinions on the output shaft and condition of the bearings and if found defective to be replaced.
- 9) Placing the output shaft assembly on the gear box .
- 10) Replacement of the oil seal of output shaft Along with O ring of end cover.
- 11) Alignment of gear box with driving pinion as per specified value.
- 12) Oil top-up in gear box up to required level and checking oil flow to bearings, gear teeth etc. through inspection doors.
- 13) Clean the work centre and remove all scraps from work centre.
- 14) Take trial run and attending defects if any found.

SERVICE LINE 290

SCOPE OF WORK:-

REPLACEMENT OF HS COUPLING OF MAIN REDUCER.

- 1) Opening of top cover of gear box.
- 2) Dismantling of gear coupling between reducer and motor.
- 3) Taking out input shaft assembly through EOT crane and placing it properly on wooden planks.
- 4) Removal of coupling halves from motor and input shaft assembly by heating.
- 5) Thorough cleaning of the coupling portion of both shafts.
- 6) Fitting new coupling halves in both shafts by heating.
- 6) Cleaning and checking of pinions on the input shaft and condition of the bearings and if found defective to be replaced.
- 7) Placing the input shaft assembly on the gear box .
- 8) Replacement of the oil seal of output shaft .
- 9) Alignment of gear box with driving pinion as per specified value.
- 10) Oil top-up in gear box up to required level and checking oil flow to bearings, gear teeth etc. through inspection doors.
- 11) Clean the work centre after completion of work.
- 12) Take trial run and attending defects if any found.

SERVICE LINE 300

SCOPE OF WORK:-

REMOVE JAMMED COAL AND SEGREGATION OF STEEL BALL.

- 1) Stop the mill.
- 2) Opening manhole doors of both DE & NDE sides.
- 3) Taking out jammed coal from hot air boxes.
- 4) Taking out coal from both side screw conveyor assembly to outside mill.
- 5) Empty the coal from mill to the required level .
- 6) Segregation of steel balls from coal taken out.
- 7) Stacking the ball separately.
- 8) Transport the ball as per E-I-C.
- 9) Transport the coal from work centre to coal yard.
- 10) Clean the work centre after completion of work.

SERVICE LINE 310

SCOPE OF WORK:-

INSPECTION MAIN BEARING AND RECTIFICATION DEFECTS.

- 1) Stop the mill.
- 2) Stop the lubrication system.
- 3) Open the access door.
- 4) Clean the nozzle after removing from place.
- 5) Repair/replace the nozzle if required.
- 6) Check the condition and position of main & support bearings.
- 7) Start the LP pump of lubrication system.
- 8) Check the oil flow after running the pump.
- 9) After found normal flow, box-up the access door.

- 10) Clean the work centre after completion of work.

SERVICE LINE 320

SCOPE OF WORK:-

REPLACEMENT OF COUNTER SHAFT BEARING OF MILL.

- 1) Stop the milling system.
- 2) Open the top cover of bearing.
- 3) Cleaning of the bearing.
- 4) Removing the side plates/ring.
- 5) Removing the burnt grease.
- 6) Removing the lock nut.
- 7) Replacement of old bearing
- 8) Transport the new bearing from central store to work centre.
- 9) Replace old bearing with new one with the help of hydraulic jack.
- 10) Taking clearances of the bearing.
- 11) Putting the lock nut, box up of the bearing after proper greasing of the bearing.
- 12) clean the work centre after completion of work.
- 13) taking trial run and attending defects if any found.

SERVICE LINE 330

SCOPE OF WORK:-

CHECKING OF ECCENTRICITY OF SHELL OF MILL.

- 1) Take PTW.
- 2) Checking eccentricity of shell with main bearing/ screw conveyor shaft.
- 3) Making alignment as per design.
- 4) If not found as per design rectify it as per design.
- 5) Clean the work centre after completion of work.

SERVICE LINE 340

SCOPE OF WORK:-

CHECKING AND RECTIFY DEFECTS OF DP BOTH SIDE OF MILL.

- 1) Positioned the mill.
- 2) Open the man hole door.
- 3) Make arrangement and scaffoldings for enter the mill.
- 4) Make arrangement of light inside of mill.
- 5) Cutting the pipes both on upper portion and lower portion of the trunion tube outside mill.
- 6) Fitting of test pipe.
- 7) Blanking the other end of the pipe, charging of the line and observing the pressure drop through the DP tube.
- 8) soap test of the jointing of the pipe.
- 9) Reassembly of the tube .
- 10) The scope of work includes dismantling of synthetic seal and its refitting.
- 11) Remove the scaffoldings and clean the work centre.

SERVICE LINE 350

SCOPE OF WORK:-

Overhauling of girth gear seal air fans and connecting pipes:-

- 1) Stop the mill and take PTW.
- 2) Removal of suction air filter.
- 3) Thorough cleaning of the filter.
- 4) Checking bearing of the fan replace if required.
- 5) Check free movement of fan Impeller.
- 6) Tightening duct flanges and body bolts.
- 7) Clean the work centre.
- 8) Take trial run and attend defects if any found.

SERVICE LINE 360

SCOPE OF WORK:-

Replacement of trunion tube of Mill

- 1) Stop the mill and take PTW.
- 2) Open man hole doors of Mill.

- 3) Cut all pc pipe.
- 4) remove hot air box by gas cutting and replace trunion tube
- 5) .Repair of hot air tube, trunion tube liner plates, angle by special lotherm-468 electrodes (DE and NDE side) of Mill.
- 6) Identifying the damaged portion of drum, removal of damaged angles, welding new angles, conveyor body, hot air box manholes doors.
- 7) Cutting of damaged skid plate and repair by welding special Lotharm-468 electrodes.
- 8) Assemble all removed parts.
- 9) Clean the work centre.
- 10) Remove all scraps from work centre to scrap yard.
- 11) Take trial run of mill and rectifying defects if any found.

SERVICE LINE 370

SCOPE OF WORK:-

REMOVAL /REPAIRING AND PLACEMENT OF HOT AIR BOX OF MILL.

- 1) Stop the mill and take PTW.
- 2) Open man hole doors.
- 3) Cut all pc pipe.
- 4) Remove hot air box by gas cutting
- 5) Identifying the damaged portion of drum.
- 6) Removal of damaged angles, welding new angles.
- 7) Repair conveyor body, hot air box, manholes doors.
- 8) Cutting of damaged skid plate and repair by welding special Lotharm-468 electrodes.
- 9) Clean the work centre.
- 10) Remove all scraps from work centre to scrap yard.
- 11) Take trial run of mill and rectifying defects if any found.

SERVICE LINE 380

SCOPE OF WORK:-

REPLACEMENT OF MAIN SPEED REDUCER GEAR BOX OF MILL.

- 1) Take PTW.
- 2) Isolate main reducer from LS and HS coupling.
- 3) Remove old gear box.
- 4) Clean the base .
- 5) Take blue matching of base of reducer and structure surface.
- 6) Transport gear box from central store to work centre.
- 7) Fit new / repaired gear box.
- 8) Opening the top inspection hole.
- 9) checking for proper spray of lubricant on gears/pinion and adjustment of lub. Oil line if needed.
- 10) Checking the flow and pr. of the reducer lub oil pump.
- 11) Backwashing of the cooler.
- 12) Cleaning of the filter.
- 13) Removal the old gear box as per E-I-C.
- 14) Clean the work centre and remove all scraps .
- 15) Taking trial run and attending defects if any.

SERVICE LINE 390

SCOPE OF WORK:-

DRAINING THE STEEL BALL FROM MILL.

- 1) Take PTW.
- 2) Positioned the mill.
- 3) Open mill main door.
- 4) Start lub oil system of Mill.
- 5) Take mill in auxiliary motor.
- 6) Drain the ball and coal inside of mill housing.
- 7) During the draining the ball and coal supervisor and helpers are present in site .

SERVICE LINE 400**SCOPE OF WORK:-**

Transportation of Hi-chrome Balls

- 1) Make arrangement for transportation of Hi chrome steel ball from central store.
- 2) Select the Hi chrome steel ball drum as per ball size.
- 3) Cutting the Hi chrome steel ball drum.
- 4) Select the place in site.
- 5) Transport the ball from central store to our site by Tractor.
- 6) Arrange the Hi chrome ball in site.
- 7) Remove all empty drums and shift in scrap yard.

SERVICE LINE 410**SCOPE OF WORK:-**

Mill-Charging of Hi-chrome balls

- 1) Start lubrication system of mill.
- 2) Take mill in Auxiliary motor.
- 3) Stop the mill after Positioned the mill.
- 4) Open man hole door of mill.
- 5) Make arrangement (Man & material) for charging Hi chrome ball.
- 6) Charge Hi chrome balls (50mm/40mm/30mm) as per instruction of E-I-C.
- 7) After charging Hi chrome balls levelled the balls .
- 8) Take mill in service (Auxiliary motor) for 10-15 minutes.
- 9) Clean the work centre after completion of work.
- 10) Remove all scraps from work place.

SERVICE LINE 420**SCOPE OF WORK:-**

Mill-Segregation steel balls & coal dust

- 1) Remove coal and Hi chrome steel ball mixture from mill housing to open space (as per E-I-C)
- 2) Manually segregate steel ball as per size, scrap ball and coal.
- 3) Transport and store balls as per size in site stock place.
- 4) Transport scraps from work place to scrap yard.
- 5) Transport coals from work centre to coal yard.
- 6) Clean the work place.

SERVICE LINE 430**SCOPE OF WORK:-**

Mill-Replace damaged ACW line valve vent

- 1) Stop ACW pump.
- 2) Drain ACW water through vents and drain valves.
- 3) Isolate the work station from water side.
- 4) Identify the damaged line and vent valves.
- 5) Cutting the vent valves/ ACW line by gas cutter.
- 6) Transport the valves and pipe line from central store to work place.
- 7) Cut the pipe line as per measurement.
- 8) Fit the pipe line/vent valve and weld it.
- 9) Removal of all scraps from work place.
- 10) Clean the work place after completion of work.

SERVICE LINE 470

Mill Shell Flange / liner bolt tightening /replacement:

Clean the threaded portion of the bolt, place the torque wrench and tighten the nut with required torque.

SERVICE LINE 480

Replacement of drive shaft of Mill:

1. Disassemble of grease panel of mill
2. Removal of coupling guard and gear coupling of Mill
3. Loosening of foundation bolts of drive shaft bearing (both DE & NDE side) and removal of bearing housing and bearing
4. Removal of gland assembly of girth gear housing and labyrinth seal after drive shaft bearing
5. locking of girth gear housing
6. Transportation of new drive shaft assembly from central store to working site

7. Removal of old drive shaft and fitting of new shaft
8. Checking for backlash of gears by lead wire method
9. checking eccentricity of mill shell and thorough alignment of drive system of Mill
10. box-up of drive system and grease panel
11. Taking trial and attending defects (if any)

SERVICE LINE 490

Scope of work- Checking and rectification of jamming between trunion and trunion tube.

1. Take permit with isolations.
2. Position the mill.
3. stop all lub oil system.
4. Open top , DE & NDE doors.
5. Remove hot air box if it require.
6. Cut four nos. of drive bars.
7. Remove screw conveyor assembly from trunion tube.
8. Remove inlet liner boss/ 'Z' liners as per requirement.
9. Clean the hi chrome steel balls and coal jamming between trunion and trunion tube.
10. After removal hi chrome steel balls and coal check the clearance and maintained as per requirement.
11. Boxed up all equipments and also fit air deflector plates.
12. Close all doors.
13. Take trial run and rectify defects if any found.
14. Clean the work center after completion work.

SERVICE LINE 500

Scope of work- Maintenance of lub oil system of milling system.

1. Take permit for lub oil system.
2. Stop all lub oil pumps.
3. Check all oil lines(04 nos for HP & 02 nos. for B&S).
4. Check all six pipe lines nozzle at the end / main bearing position.
5. Check all hose pipes and replace if required.
6. Check all NRVs and replace if required.
7. Check all T-Joints and replace if required.
8. Check all couplings of pumps and replace if required.
9. Check oil level in main oil compartment and top-up if required.
10. Clean the work center after completion of work.

SERVICE LINE 510

Scope of work- maintenance of main reducer gear box.

1. Take permit of equipment with safety isolation.
2. Stop all lub oil system of main reducer gear box.
3. Open top half cover of main reducer gear box.
4. Check all bearings and clearance of bearings.
5. Check all oil seals.
6. check all oil nozzles and if required clean it.
7. Check all gears .
8. Decouple the coupling both LS & HS.
9. Clean the teeths of LS coupling and springs of HS coupling.
10. Fit both couplings after greasing.
11. Check reducer lub oil pump, coupling and replace as per requirement.
12. Clean both oil filter.
13. Take trial run of lub oil pumps and check oil flow in all points.
14. Close the top half cover of main reducer gear box.
15. Take in aux. motor and check from inspection door.
16. Clean the work center after completion of work.

SERVICE LINE 520

Replacement all shell joint bolts of mill

TOTAL NUMBER OF BOLTS-60 WITH 60 NUMBERS OF LOCKING.

Scope work- Replacement all shell bolts of mill.

- 1) Cut all lockings of shell around 60 numbers from one side by gas cutting.
- 2) Clean shell joints area.

- 3) Transport new shell bolts from central store.
- 4) Loosen continue three shell bolts .
- 5) After loosen three bolts , remove middle bolt and fit new bolt.
- 6) Then remove one by one bolt with replacement bolts. (60 numbers)
- 7) Tighten all new bolts as per requirement .
- 8) After full tighten the bolts , lock all 60 numbers of lock.
- 9) After completion the work clean work center.

SERVICE LINE 530

Repairing of coal retaining plates of R.C. feeders

Identifying the damaged portion, making V cut by grinding and repair by welding with SS electrode

SERVICE LINE 540

SCOPE OF WORK:-

Overhauling of R.C. Feeder:-

- 1) Opening front , rear and side doors of the R.C. Feeder.
- 2) Removal of coal from feeder.
- 3) Feeder belt checking, feeder internal checking and removal of foreign particles from feeders (like wires etc.).
- 4) Checking for the freeness of the rollers.
- 5) Greasing of all bearings including COC, COC zone clearness checking.
- 6) Chain adjustment and trial run.
- 7) Oil level checking of feeder belt drives GB.
- 8) Oil level checking of cleanout conveyor GB.
- 9) Front & rear door gaskets & uplift washers checking.
- 10) Side door gaskets checking.
- 11) Both reducers outside cleaning.
- 12) Feeder belt tension adjustment.
- 13) Removal of all scraps from work centre.
- 14) Clean the work centre after completion of work.

SERVICE LINE 550

SCOPE OF WORK:-

REPLACE OF DAMAGED BELT OF RAW COAL FEEDERS

- 1) Opening front, rear and side doors of the R.C. feeder.
- 2) Removal of jammed coal from the feeder and simultaneously closing the feeder inlet gate.
- 3) Removal of all the greasing hoses and load cells connections.
- 4) Removal of belt tensioning pulley.
- 5) Span rollers, other rollers.
- 6) Dismantling of drive pulley.
- 7) taking out drive pulley.
- 8) Taking out the belt.
- 9) Reassembly of the feeder with repaired/ new belt.
- 10) Trial run of the feeder, adjustment of belt and box-up of the feeder.
- 11) Removal of all scraps from work centre.
- 12) Clean the work place after completion of work.

SERVICE LINE 560

SCOPE OF WORK:-

REPLACEMENT OF RAW COAL FEEDER MAIN GEAR BOX.

- 1) Open side door of raw coal feeder.
- 1) Dismantling of gear box by opening of all nut and bolts with feeder body .
- 2) Taking it out with help of chain block.
- 3) Replacement of damaged parts to be done if fitted old including bearing and oil seals ,Flange and pins of old gear box .
- 3) Transport new /repaired gear box.
- 4) Fit new gear box and positioning of new gear box to be fitted with drive rollers.
- 5) Oil top- up in gear box to be ensured.
- 6) Chain tension adjustment/replacement with chain links.
- 7) Take trial run and rectify if found any abnormalities.
- 8) Removal of old gear box as per E-I-C.
- 9) Clean the work place after completion.

SERVICE LINE 570**SCOPE OF WORK:-**

REPLACEMENT OF CLEAN OUT CONVEYOR GEAR BOX OF RAW COAL FEEDER.

- 1) Open side door of raw coal feeder.
- 2) Dismantling of gear box by opening of all nut and bolts with feeder body and taking it out with help of chain block.
- 3) Servicing and replacement of damaged parts to be done if fitted old including bearing and oil seals Flange and pins of old gear box.
- 4) Fitted old bearing and oil seals Flange and pins of old gear box in new gear box .
- 5) Positioning of new gear box to be fitted with drive rollers.
- 6) Oil top- up in gear box to be ensured.
- 7) Chain tension adjustment/ replacement with chain links.
- 8) Close the side door.
- 9) Take trial run and rectify if found any abnormalities.
- 10) Clean the work place after completion.

SERVICE LINE 580

O/H of raw coal feeder clean out conveyor gear box.

- 1) Dismantling of gear box by opening of all nut and bolts. 2) Servicing and replacement of damaged parts to be done if fitted old including bearing and oil seals otherwise replaced with new bearings and seals.
- 3) Flange and pins of old gear box to be fitted in new gear box.
- 4) Oil top up in gear box.
- 5) Check freeness of gear box.
- 6) Transport repaired gear box from their works to our site.

SERVICE LINE 590

O/H of raw coal feeder gear box main.

- 1) Dismantling of gear box by opening of all nut and bolts. 2) Servicing and replacement of damaged parts to be done if fitted old including bearing and oil seals otherwise replaced with new bearings and seals.
- 3) Flange and pins of old gear box to be fitted in new gear box.
- 4) Oil top up in gear box.
- 5) Check freeness of gear box.
- 6) Transport repaired gear box from their works to our site.

SERVICE LINE 610

Internal checking of R.C. Feeder

Feeder belt checking, feeder internal checking and removal of foreign particles from feeders (like wires etc.), checking for the freeness of the rollers, greasing of all bearings including COC, COC zone clearness checking, chain adjustment and trial run, oil level checking of feeder belt drive GB, oil level checking of clean out conveyor GB, front & rear door gaskets & uplift washers checking, side door gaskets checking, both reducer outside cleaning, feeder belt tension adjustment.

SERVICE LINE 620

Mill-remove the inlet valve, disconnect the pipe, checking the line and valve of seal air fans and connecting pipes & fitting the valve.

SERVICE LINE 630**Scope of work-**

1. Open both side doors of RC FEEDER.
2. Decouple the COC gear box .
3. Removal other end shaft.
4. Remove all damaged chain/ part of damaged chain.
5. Fix the new chain as per requirement.
6. Check all joints pin .
7. Take trial run of COC and rectify if any defects found.
8. Close the doors.
9. Clean the work center.

SERVICE LINE 640

Scope of work.

1. Open all four side doors of Rc feeder.
2. Run the feeder in local mode and empty the RC feeder.
3. Remove all Gaskets from doors.
4. Transport the rubber gasket/ rubber seal from central store to work center.
5. Clean the gasket surface.
6. Cut the rubber gasket/ rubber seal as per diamantion & end profile.
7. Fit the rubber gasket/ rubber seal and fix it.
8. Close all doors after completion of work.
9. Open coal inlet damper.
10. Remove all scraps from work center.

SERVICE LINE 650**SCOPE OF WORK:-**

CLASSIFIER- INTERNAL CHECKING OF CLASSIFIER/ CONE.

- 1) Open the door of both side of the outer cone.
- 2) Open Inner cone and the classifier doors.
- 3) Arrange for lighting and Platforms as required.
- 4) Thorough cleaning of inside and outside of the classifiers.
- 5) Checking for any erosion to classifier body ,internal cones.
- 6) Checking the position of classifiers vanes and box up of classifiers.
- 7) Opening the classifier return line man hole.
- 8) Cleaning of any jamming, checking condition of the flappers, and box up of the return lines .
- 9) Disposal of all the scrap /foreign materials arising out of this work.
- 10) Clean the work place after completion of work.

SERVICE LINE 660**SCOPE OF WORK:-**

- 1) Open the door of both side of the outer cone.
- 2) Open Inner cone and the classifier doors.
- 3) Arrange for lighting and Platforms as required.
- 4) Thorough cleaning of inside and outside of the classifiers.
- 5) Erection of temporary scaffolding.
- 6) Identify the damaged portion and take measurement of damaged part.
- 7) Cutting of Plates in required size.
- 8) Bending of the plate.
- 9) Jacketing around the connecting duct and welding by M.S..
- 10) Removal of temporary scaffolding.
- 11) Removing leaked coal/ash dust and scraps.
- 12) Clean the work place after completion of work.

SERVICE LINE 670**SCOPE OF WORK:-**

Fitting of NRV flapper in classifiers

- 1) Open the classifier door and side door.
- 2) Opening of clack box .
- 3) Dismantling and removal of old & damaged NRV flapper.
- 4) Fabrication of new flapper as per old NRV flapper.
- 5) Fitting of new flapper .
- 6) Check the proper working of NRV flapper.
- 7) Box up of the clack box.
- 8) Box up the classifier.
- 9) Removal all scraps and clean the work place after completion of work.

SERVICE LINE 690**SCOPE OF WORK:-**

REMOVAL AND FITTING OF CLASSIFIER UPPER AND LOWER CONE.

- 1) Opening of the manhole doors.
- 2) Removal of the damaged cones by gas cutting.

- 3) Shifting of the prefabricated cones to the classifier.
- 4) Positioning of these cones with respect to upper cone.
- 5) Fitting by welding, closing of the doors.
- 6) Removal of all the scrap materials from worksite.
- 7) Scope of work also includes repair of damaged portion of stiffener plates and classifier body.
- 8) Clean the work place after completion of work.

SERVICE LINE 699

Removal of damaged venturi of classifier and it's fitting after repairing.

SERVICE LINE 700

SCOPE OF WORK:-

Attending coal dust leakage from punctured coal pipe of different location from Mill O/L .

Erection of scaffolding around coal pipes for attending leakages from them, repairing of punctured coal pipe of different elevation by doing patch work by welding new patches of coal pipes (Ø 558 x 14.2mm) in running condition of Unit.

SERVICE LINE 710

SCOPE OF WORK:-

ARRESTING COAL DUET LEAKAGE FROM COAL INLET PIPE OF MILL BY SS WELDING.

- 1) Erection of scaffolding around coal pipes for attending leakages from them.
- 2) Repairing of punctured coal pipe of different elevation by doing patch work by SS welding new patches of coal pipes (Ø 558 x 14.2mm) in running condition of Unit.

SERVICE LINE 720

Scope of work-

1. Identify the job.
2. Open the doors both upper & lower of classifier.
3. Arrange lighting.
4. Make platform for work at height.
5. Thorough cleaning of inside and out side of classifier.
6. Checking for any damage refractory.
7. Removal of damaged refractory.
8. Transport refractory from central store to work center.
9. Reapplication with new refractory.
10. As per requirement also reapplication refractory at mill out let.
11. Clean the work center.

SERVICE LINE 730

SCOPE OF WORK:-

GAS/GRINDER CUTTING OF DAMAGED/ERODED ACW PIPE LINE, PLACEMENT/ FITTING OF NEW PIPE OF SAME SIZE, MS WELDING OF PIPE, REMOVAL OF SCRAP TO SCRAP YARD, IF REQUIRED, SCAFFOLDING ERECTION. REPAIRING OF ACW PIPE LINE BY COVERING IT WITH MS PLATE AND MS WELDING.

SERVICE LINE 740

Assistance of manpower to meet various emergency e.g. during Lit-up various problems is necessary to be attended like leakage from oil line, maintaining proper flow till normalisation of system etc.

Detail of manpower is as follows:-

(a) Man power engaged by agency

sl. No.	TYPE	NO.LABOUR	SHIFT	DAYS	MANDAYS	RATE	AMOUNT
1	Helper/U.S.labour	2	1	1	2	488.79	977.58

Total Rs.= 977.58

CP & T & P @11% 107.5338

1085.1138

SERVICE LINE 760

Assistance of manpower to meet various emergency e.g. during Lit-up various problems is necessary to be attended like leakage from oil line, maintaining proper flow till normalisation of system etc.

SERVICE LINE 770

Assistance of manpower to meet various emergency e.g. during Lit-up various problems is necessary to be attended like leakage from oil line, maintaining proper flow till normalisation of system etc.



TENUGHAT VIDYUT NIGAM LIMITED

तेनुघाट विद्युत निगम लिमिटेड

(A Govt. of Jharkhand Undertaking)

JUPMI Building premises in ABD Area, Ranchi SmartCity, P.O&P.S.Dhurwa, Ranchi-04, (Jharkhand)

BILL OF QUANTITY

PART – II (PRICE PART)

NIT No. 28/BMD/W/TVNL/RAN/2025-26.
SRM RFx No-1000012040

Sub: Annual Rate Contract for 02 (Two) years and annual overhauling of Mills BBD 4760 BIS, Raw Coal Feeders, Classifiers etc of Unit-1&2 of TTPS, Lalpania.

Sl No	Description of work	Qnty.	Unit	Rate (Rs.)	Amount (Rs.)
1	ARC for (2yrs) & Annual O/H of Mills BBD 4760 BIS, Raw Coal Feeders, Classifiers etc of Unit-1&2 of TTPS, Lalpania.	1.000	AU		
Total					

Part-II: - Price bid to be submitted in TVNL SRM website only.

(Certificate in Bank Letter Head)

SOLVENCY CERTIFICATE

BANK NAME /BANK SEAL

BRANCH.....

DATE.....

To,

.....

.....

.....

This is to certify that to the best of our knowledge and information that
Mr/Mrs/Ms/Company Name/Firm Name.....a customer of our bank
having Account type.....and Number.....is respectable
and can be treated solvent up to a sum of
Rs.....(Rupees.....Only).

Branch Manager

Sign

Seal of Bank